

AMENDMENT OF SOLICITATION/MODIFICATION OF CONTRACT				1. CONTRACT ID CODE <div style="text-align: center;">J</div>		PAGE OF PAGES <div style="text-align: center;">1 3</div>	
2. AMENDMENT/MODIFICATION NO. <div style="text-align: center;">0002</div>		3. EFFECTIVE DATE <div style="text-align: center;">20-May-2004</div>		4. REQUISITION/PURCHASE REQ. NO. <div style="text-align: center;">W81D4A-04</div>		5. PROJECT NO.(If applicable)	
6. ISSUED BY CONTRACTING DIVISION 69-A HAGOOD AVE CHARLESTON SC 29403-5107		CODE <div style="text-align: center;">W912HP</div>		7. ADMINISTERED BY (If other than item 6) <div style="text-align: center; font-weight: bold;">See Item 6</div>			
8. NAME AND ADDRESS OF CONTRACTOR (No., Street, County, State and Zip Code)				<input checked="" type="checkbox"/> 9A. AMENDMENT OF SOLICITATION NO. W912HP-04-B-0005			
				<input checked="" type="checkbox"/> 9B. DATED (SEE ITEM 11) 28-Apr-2004			
				10A. MOD. OF CONTRACT/ORDER NO.			
				10B. DATED (SEE ITEM 13)			
CODE		FACILITY CODE					
11. THIS ITEM ONLY APPLIES TO AMENDMENTS OF SOLICITATIONS							
<input checked="" type="checkbox"/> The above numbered solicitation is amended as set forth in Item 14. The hour and date specified for receipt of Offer <input type="checkbox"/> is extended, <input checked="" type="checkbox"/> is not extended. Offer must acknowledge receipt of this amendment prior to the hour and date specified in the solicitation or as amended by one of the following methods: (a) By completing Items 8 and 15, and returning <u>1</u> copies of the amendment; (b) By acknowledging receipt of this amendment on each copy of the offer submitted; or (c) By separate letter or telegram which includes a reference to the solicitation and amendment numbers. FAILURE OF YOUR ACKNOWLEDGMENT TO BE RECEIVED AT THE PLACE DESIGNATED FOR THE RECEIPT OF OFFERS PRIOR TO THE HOUR AND DATE SPECIFIED MAY RESULT IN REJECTION OF YOUR OFFER. If by virtue of this amendment you desire to change an offer already submitted, such change may be made by telegram or letter, provided each telegram or letter makes reference to the solicitation and this amendment, and is received prior to the opening hour and date specified.							
12. ACCOUNTING AND APPROPRIATION DATA (If required)							
13. THIS ITEM APPLIES ONLY TO MODIFICATIONS OF CONTRACTS/ORDERS. IT MODIFIES THE CONTRACT/ORDER NO. AS DESCRIBED IN ITEM 14.							
A. THIS CHANGE ORDER IS ISSUED PURSUANT TO: (Specify authority) THE CHANGES SET FORTH IN ITEM 14 ARE MADE IN THE CONTRACT ORDER NO. IN ITEM 10A.							
B. THE ABOVE NUMBERED CONTRACT/ORDER IS MODIFIED TO REFLECT THE ADMINISTRATIVE CHANGES (such as changes in paying office, appropriation date, etc.) SET FORTH IN ITEM 14, PURSUANT TO THE AUTHORITY OF FAR 43.103(B).							
C. THIS SUPPLEMENTAL AGREEMENT IS ENTERED INTO PURSUANT TO AUTHORITY OF:							
D. OTHER (Specify type of modification and authority)							
E. IMPORTANT: Contractor <input type="checkbox"/> is not, <input type="checkbox"/> is required to sign this document and return _____ copies to the issuing office.							
14. DESCRIPTION OF AMENDMENT/MODIFICATION (Organized by UCF section headings, including solicitation/contract subject matter where feasible.) The purpose of this amendment is to add specification sections 08210 (Wood Door) and 09650 (Resilient Flooring) and respond to questions concerning IFB, W912HP-04-B-0005, Jackson Barricade Replacement Project, Savannah River Site, Aiken County, South Carolina. Please see Continuation Page(s) for Questions and Answers.							
Except as provided herein, all terms and conditions of the document referenced in Item 9A or 10A, as heretofore changed, remains unchanged and in full force and effect.							
15A. NAME AND TITLE OF SIGNER (Type or print)				16A. NAME AND TITLE OF CONTRACTING OFFICER (Type or print)			
				TEL: _____ EMAIL: _____			
15B. CONTRACTOR/OFFEROR _____ (Signature of person authorized to sign)		15C. DATE SIGNED		16B. UNITED STATES OF AMERICA BY _____ (Signature of Contracting Officer)		16C. DATE SIGNED 20-May-2004	

SECTION SF 30 BLOCK 14 CONTINUATION PAGE

SUMMARY OF CHANGES

(End of Summary of Changes)

The following items are applicable to this modification:

QUESTIONS AND ANSWERS - Please notice additional "Notes" to the drawings.**1. What size is the existing waterline on the C-road?**

According to existing site maps, the existing water line is 1 1/2" PVC. **Add the following note to drawings, sheet C-9 and C-10:** "Contractor is required to verify size and location of all utilities prior to construction as required for the performance of work under this contract." **Revise the existing drawing note for the water line on sheet C-9 to read** " Existing 1½" water service line (Location Approximate)."

2. What type of pipe material for the 1-1/2" service line?

Add the following note to drawings, sheet C-9 and C-10:

"Unless otherwise shown or noted in the contract documents the 1 1/2" water service line shall be PCV."

3. Will existing paving remain from new overlay area to existing edge of pavement as shown on plan C-11, C-12 & C-13?

Existing paving will remain from new overlay area to existing edge of pavement as shown on plan C-11, C-12 & C-13.

4. Will we be able to dispose of material on site at the C& D landfill or will all waste be disposed off-site?

All material shall be disposed of off-site unless otherwise noted in the specifications.

5. Are there any SCADA or fiber optics concerns along C-Road?

There are no known SCADA or fiber optic concerns along "C" road; however, contractor is required to verify size and location of all utilities prior to construction as required for the performance of work under this contract.

6. Who will be responsible for GPR, the subcontractor or site facilities?

GPR will not be performed by site forces or the government. The contractor will be responsible for determining the size and location of all utilities prior to the start of physical construction as required for performance of work under this contract.

7. Will the contractor be required to sign onto the Project agreement?

Project labor agreement is not required for this contract.

8. Are the counters, book shelves, metal storage cabinet & shelf for the radio/CCTV in the administrative building included in this bid? If so please provide specifications.

Add the following note to drawings, sheet A-1: "The counters, book shelves, metal storage cabinet & shelf for the radio/cctv are to be provided by the user and are not included in this contract."

9. Is the door in the bathroom aluminum like the main entrance door? If not please provide the specifications.

The door to the bathroom shall be wood 3'-4" w X 7' h. Door shall be as specified in the attached specification 08210.

10. No specifications given for the VCT flooring & the Base in the administrative building.

The VCT flooring & base specification shall be as specified in attached specification section 09650.

11. No spec section given for the guard house.

The Tollbooths specifications are stated in the notes on sheet A5. The administration building specifications are stated in the contract documents.

12. No spec section given for letters on sign.

Lettering information on the entrance sign is shown on drawing A6.

13. No spec section given for the stone on the sign.

Add the following note to drawings, sheet A-6, Note 4: "The pre-fabricated stone finish shall be 1.5' h X 6' l X 3/4" thk Sandstone color to match building. Panel: #EY25138 Corner: #JEY25138K by Nichiha wall systems or approved equal."

14. Does stone go on backside of sign?

See drawing A7. There is a Section through the sign that shows the stone on the backside.

15. Makeup of walls on the interior of the building not given.

Add the following note to drawings, sheet A-1: "The interior surface of exterior walls shall be painted CMU. Interior partition walls shall be steel studs and gypsum board with painted finish unless otherwise specified or noted."

16. No spec section on flagpoles.

Add the following note to drawings, sheet A-2: "Flagpoles shall be Poletch Architectural Flagpoles or an approved equal. Durable one-piece cone tapered 6063-T6 seamless extruded aluminum Satin brush. Equipment included: Gold anodized 14 ga. aluminum ball. Revolving non-fouling, cast alum. truck with one aluminum sheave. Two 3.5" brass swivel type snaphook per one halyard. 9" cast alum. cleat one per halyard."

17. Does 16 gauge decking go under the standing seam roof of the building?

Yes. **Add the following note to drawings, sheet J-1:** "The Standing Seam Metal Roof shall be clipped to the metal decking."

18. Where is the transite (Bid Item 0011) and how much is there?

The Transite is throughout the building. There is approximately 560 sq. ft. of asbestos. This is only an approximate figure.

19. Do slabs for Guard shacks and sidewalks have rebar/wire mesh in them?

No, the slab and the sidewalks do not have rebar or wire mesh.

20. Do guard shack slabs have footers below grade? If not how thick are these slabs?

Add the following note to drawings, sheet A-5, Note 2: " Slabs for shelters shall be provided with turndown slab at edges. Turndown shall be 1'-0" thick (as measured from top of slab) and extend inward toward center of slab a distance of 1'-0". "